12 MAI 2017



SPECIFICATIONS

1. LUBE SYSTEM NOMINAL PRESSURE : 6bar.
2. LIFT SYSTEM NOMINAL PRESSURE : 315bar
3. LUBE SYSTEM NOMINAL FLOWRATE: 160L/min.
4. LIFT SYSTEM NOMINAL FLOWRATE: 10L/min*4.
5. FLUID : ISOVG460.
6. OIL VISCOSITY : 460CST AT 40°C.
7. OPERATING TEMPERATURE RANGE : 43°C±2°C.
8. POWER SOURCE:
   MOTOR : 400VAC/50HZ/3PH
   HEATER : 400VAC/50HZ

SEQ.	APPLICATION	DESCRIPTION	QTY.	MADE	REMARK
37	Pressure transmitters	[illegible]	1	ROSEMOUNT	
36	Filter switches	[illegible]	4	[illegible]	
35	Two piece type full valves	[illegible]	4	HUPIAN	
34	Ball valves	[illegible]	4	PARKERSIMMA	
33	Thermometer	[illegible]	1	ASHCROFT	
32	Solid temperature control valve	[illegible]	1	[illegible]	
31	Y type strainer	[illegible]	1	HUPIAN	
30	Check valves	[illegible]	4	HUADE	
29	Plate cooler	[illegible]	1	SRP	
28	Restriction flowing plates	[illegible]	4	REXROTH	
27	Butterfly valves	[illegible]	5	HUPIAN	
26	Duplex filter	[illegible]	1	INTERNORMEN	
25	Duplex filter	[illegible]	1	INTERNORMEN	
24	Stainless pressure gauges	[illegible]	2	WIKA	
23	Stainless pressure gauges	[illegible]	2	WIKA	
22	Needle valve	[illegible]	1	[illegible]	
21	Relief valve	[illegible]	1	REXROTH	
20	Check valves	[illegible]	2	HUPIAN	
19	Butterfly valves	[illegible]	5	HUPIAN	
18	Safety valve	[illegible]	1	[illegible]	
17	Shock absorber	[illegible]	2	HUPIAN	
16	Check valves	[illegible]	2	HUADE	
15	Flexible oil switch	[illegible]	1	[illegible]	
14	Low pressure pumps with motor	[illegible]	2	SETTINGMEMBER	
13	Air filters	[illegible]	2	HUADE	
12	Armoured hot resistance	[illegible]	2	[illegible]	
11	High pressure pumps with motor	[illegible]	2	PARKERSIMMA	
10	Pressure transmitters	[illegible]	5	ROSEMOUNT	
9	Ball valves with limit switch	[illegible]	2	HUPIAN	
8	Level gauge	[illegible]	1	HUADE	
7	Thermometer	[illegible]	1	ASHCROFT	
6	Armoured hot resistance	[illegible]	1	[illegible]	
5	Temperature switch	[illegible]	1	ASHCROFT	
4	Rotary oil magnetic filters	[illegible]	4	LINCOLN	
3	Oil tank	[illegible]	1	LINCOLN	
2	Electric heaters	[illegible]	6	YUANPAN	
1	Two piece type full valves	[illegible]	3	HUPIAN	

TITLE

PROCESS AND INSTRUMENTATION DIAGRAM
INTLET SLIDE SHOE BEARING OF Φ4,4×14+3,8x3,5m CEMENT MILL
LIFT AND LUBE OIL SYSTEM

DRAWING No.	LAC-LLS-OCS-005-02-00000	REV.	FINAL
QTY.	2	SIZE	A3
SCALE	NONE	DATE	22 Mar. 2013
WEIGHT	NONE		
MATERIAL	NONE		
PART No.	NONE		

REV. DESCRIPTION BY APP. DATE

LINCOLN INDUSTRIAL CORPORATION